

MARAPONE SAMPLE - RETAIL TENANT FIT-OUT  
PRELIMINARY DESIGN SET - NOT FOR CONSTRUCTION

SHEET INDEX

A-101 FLOOR PLAN

A-201 INTERIOR ELEVATIONS

A-501 DOOR AND WINDOW SCHEDULES

A-601 ROOM FINISH SCHEDULE

P-101 PLUMBING FIXTURE PLAN

# ROOM FINISH SCHEDULE

| ROOM NAME         | AREA    |
|-------------------|---------|
| SALES FLOOR       | 1840 SF |
| STOCKROOM         | 620 SF  |
| FITTING ROOMS     | 180 SF  |
| BREAK ROOM        | 148 SF  |
| MANAGER OFFICE    | 120 SF  |
| RECEIVING         | 240 SF  |
| STAFF RESTROOM    | 64 SF   |
| PUBLIC RESTROOM A | 72 SF   |
| PUBLIC RESTROOM B | 72 SF   |
| JANITOR CLOSET    | 36 SF   |
| VESTIBULE         | 96 SF   |
| CORRIDOR          | 210 SF  |

DOOR SCHEDULE

| MARK | SIZE          | TYPE                  | QTY   |
|------|---------------|-----------------------|-------|
| D1   | 3'-0" x 7'-0" | STOREFRONT ALUMINUM   | QTY 2 |
| D2   | 3'-0" x 7'-0" | INTERIOR SOLID CORE   | QTY 9 |
| D3   | 2'-8" x 6'-8" | INTERIOR HOLLOW CORE  | QTY 5 |
| D4   | 6'-0" x 7'-0" | EXTERIOR RECEIVING HM | QTY 1 |

WINDOW SCHEDULE

| MARK | SIZE          | TYPE             | QTY   |
|------|---------------|------------------|-------|
| W1   | 4'-0" x 6'-0" | STOREFRONT FIXED | QTY 7 |
| W2   | 2'-0" x 2'-0" | CLERESTORY       | QTY 4 |

# PLUMBING FIXTURE SCHEDULE

|                 |       |
|-----------------|-------|
| WATER CLOSET    | QTY 4 |
| LAVATORY        | QTY 4 |
| MOP SINK        | QTY 1 |
| BREAK ROOM SINK | QTY 1 |
| WATER HEATER    | QTY 1 |
| FLOOR DRAIN     | QTY 3 |